

**SHOPPA'S**  
MATERIAL HANDLING

**Ai** ADVANCED  
INTRALOGISTICS

**UPRIGHT**



**REPLACE**

VS.



**REPAIR**



**REPLACE**

VS.



**REPAIR**

Unload 20 pallets and stage out of the way	<b>45 mins</b>
Install crew must utilize equipment to disassemble upright and wire decks	<b>45 mins</b>
Anchors cut, install new uprights, beams & wire deck, then anchor.	<b>45 mins</b>
Reload all pallets	<b>45 mins</b>
Materials Shipment	<b>2-3 Days</b>

**LEAD TIME: 3+ DAYS**

## Cost Breakdown

NEW 42" x 240" Upright	<b>\$265</b>
(2) 1/2" Anchors	<b>\$4</b>
Local Delivery	<b>\$250</b>
Labor	<b>\$575</b>
Equipment Rental & Delivery	<b>\$990</b>

**COST: \$2,084**

Unload 2-8 pallets and stage out of the way <small>(*total load must not exceed 10,000 lbs)</small>	<b>20 mins</b>
Install crew raise the upright and cut out damage	<b>15 mins</b>
Anchors cut, install repair kit, then anchor.	<b>30 mins</b>
Reload all pallets	<b>20 mins</b>
Materials Shipment	<b>1 Day</b>

**LEAD TIME: 1 DAY**

## Cost Breakdown

24" Repair Kit	<b>\$575</b>
(4) 3/4" Anchors	<b>Included</b>
Local Delivery	<b>\$75</b>
Labor	<b>\$250</b>
Equipment Rental & Delivery	<b>No need!</b>

**COST: \$900**

*This comparison is based on standard in-stock repair kit for damaged 20' tall upright with 4 beams levels and wire deck.*

**TOTAL COST SAVINGS: \$1,184+**

## REPAIR KIT BENEFITS

- Lead time savings up to **48+ hours**
- Install time savings up to **1.5+ hours**
- Anchors installed in between front and back column eliminate any problems that may occur with existing upright footplate anchor hole or damaged concrete.

## Contact Us

**866.506.2200**  
shoppasmaterialhandling.com

**800.992.1431**  
advancedintralogistics.com